

## Brook Road - Site #2

### Work to be performed:

Down by Joe Compos - West side of road. Replace culvert, fix outlet. Town to supply culvert.

### Dimensions:

Length Along Road:	25 Feet
Width Along Slope	10 Feet
Ditch Width:	Feet
Stone Depth:	4 Feet

### Culvert Quantities:

Culvert:	36" CPEP	40.0 LF	Cost includes installation of pipe
----------	----------	---------	------------------------------------

### Ditch Quantities:

Excavation:	CY
Stone Fill, Type 1:	CY

### Slope Quantities

Excavation:	37.0 CY
Stone Fill, Type IV	37.0 CY