

Hook Road - Site #2

Work to be performed:

By Cemetery - Fix shoulder of road and ditch, Replace Culvert. Town to supply and haul material.

Dimensions:

Length Along Road:	1320 Feet
Width Along Slope	0 Feet
Ditch Width:	8 Feet
Stone Depth:	0 Feet
Roadway Width:	2 Feet

Culvert Quantities:

Culvert: 30" CPEP	40.0 LF
-------------------	---------

Ditch Quantities:

Excavation:	391.1 CY
Stone Fill, Type 1:	391.1 CY
1 - 1/2" Crushed Stone	195.6 CY

Slope Quantities

Excavation:	0.0 CY
Stone Fill, Type IV	0.0 CY

Roadway Quantities:

Roadway Material - 1-1/4" Plant Mix	48.9 CY	Town to perform road surface
-------------------------------------	---------	------------------------------