Jenkins Brook - Site #1

Work to be performed:

By Jenkins Brook Road. Stone around bridge wingwall, fix scour at road edge and resurface roadway.

Di	m	е	n	SI	o	n	S	١

Length Along Road:	135 Feet
Width Along Slope	0 Feet
Ditch Width:	0 Feet
Stone Depth:	0 Feet
Roadway Width:	20 Feet

Culvert Quantities:

Culvert: LF

Ditch Quantities:

Excavation:	0.0 CY
Stone Fill, Type 1:	0.0 CY
1 - 1/2" Crushed Stone	0.0 CY

Slope Quantities

Excavation:	0.0 CY	
Stone Fill, Type IV	15.0 CY	At bridge abutment
Stone Fill, Type 1	15.0 CY	At bridge abutment

Roadway Quantities:

Roadway Material - 1-1/4" Plant Mix	50.0 CY	Town to perform road surface