

Jenkins Brook - Site #2

Work to be performed:

Between Metcalfs and Hall Road - various locations. Two new culverts - 1 - 30" and 1 - 18". Repair various sections of ditch and road shoulder. Town to supply and haul material.

Dimensions:

Length Along Road:	2000 Feet
Width Along Slope	0 Feet
Ditch Width:	6 Feet
Stone Depth:	0 Feet
Roadway Width:	5 Feet

Culvert Quantities:

Culvert: 18" CPEP	40.0 LF
30" CPEP	40.0 LF

Ditch Quantities:

Excavation:	444.4 CY
Stone Fill, Type 1:	444.4 CY
1 - 1/2" Crushed Stone	222.2 CY

Slope Quantities

Excavation:	0.0 CY
Stone Fill, Type IV	CY
Stone Fill, Type 1	CY

Roadway Quantities:

Roadway Material - 1-1/4" Plant Mix	46.3 CY	Town to perform road surface
-------------------------------------	---------	------------------------------