

Pent Road

Work to be performed:

By Coburn's. Replace undersized culvert and stone lined ditching. Town to supply and haul material.

Dimensions:

| | |
|--------------------|----------|
| Length Along Road: | 550 Feet |
| Width Along Slope | 0 Feet |
| Ditch Width: | 8 Feet |
| Stone Depth: | 0 Feet |
| Roadway Width: | 5 Feet |

Culvert Quantities:

| | |
|-------------------|---------|
| Culvert: 30" HDPE | 40.0 LF |
|-------------------|---------|

Ditch Quantities:

| | |
|------------------------|----------|
| Excavation: | 163.0 CY |
| Stone Fill, Type 1: | 163.0 CY |
| 1 - 1/2" Crushed Stone | 81.5 CY |

Slope Quantities

| | |
|---------------------|--------|
| Excavation: | 0.0 CY |
| Stone Fill, Type IV | CY |
| Stone Fill, Type 1 | CY |

Roadway Quantities:

| | | |
|-------------------------------------|---------|------------------------------|
| Roadway Material - 1-1/4" Plant Mix | 50.9 CY | Town to perform road surface |
|-------------------------------------|---------|------------------------------|