

## South Washington Road - Site #2

### Work to be performed:

Second site north of Upper Village Road, right side of road. Repair slope at brook. Steep embankment, use stone toe wall detail.

### Dimensions:

Length Along Road:	60 Feet
Width Along Slope	10 Feet
Ditch Width:	0 Feet
Stone Depth:	4 Feet
Roadway Width:	0 Feet

### Culvert Quantities:

Culvert:	0.0	LF	Cost of all excavation and roadway material for installation.
----------	-----	----	---

### Ditch Quantities:

Excavation:	0.0 CY
Stone Fill, Type 1:	0.0 CY
1 - 1/2" Crushed Stone	0.0 CY

### Slope Quantities

Excavation:	88.9 CY
Stone Fill, Type IV	88.9 CY

### Roadway Quantities:

Roadway Material - 1-1/4" Plant Mix	0.0 CY
-------------------------------------	--------