

## South Washington Road - Site #1

### Work to be performed:

First site north of intersection with Upper Village Road. Replace Culvert and repair roadway slope.  
Town to supply culvert.

### Dimensions:

Length Along Road:	120 Feet
Width Along Slope	12 Feet
Ditch Width:	0 Feet
Stone Depth:	4 Feet
Roadway Width:	0 Feet

### Culvert Quantities:

Culvert: 30" CPEP	40.0	LF	Cost of all excavation and roadway material for installation.
-------------------	------	----	---

### Ditch Quantities:

Excavation:	0.0 CY
Stone Fill, Type 1:	0.0 CY
1 - 1/2" Crushed Stone	0.0 CY

### Slope Quantities

Excavation:	213.3 CY
Stone Fill, Type IV	213.3 CY

### Roadway Quantities:

Roadway Material - 1-1/4" Plant Mix	0.0 CY
-------------------------------------	--------