Upper Village Road - Mudslide

Work to be performed:

Mudslide - Remove debris and restablish the ditch on the north side of road. Remove debris/trees from south (brook) side of road and restablish slope. Slope work is undetermined on brook side until debris is removed - stone fill is estimated at this time.

		•
II)ım	anc	ions:
ווווטו	CIIS	iviis.

150 Feet
0 Feet
8 Feet
0 Feet
0 Feet

Debris Removal (Approximate Estimate): 1000 CY

Culvert Quantities:

Culvert: LF

Ditch Quantities:

Excavation:	44.4 CY
Stone Fill, Type 1:	44.4 CY
1 - 1/2" Crushed Stone	22.2 CY

Slope Quantities

Excavation: 0.0 CY
Stone Fill, Type IV 200.0 CY

Roadway Quantities:

Roadway Material - 1-1/4" Plant Mix 0.0 CY